



Pedestrian Countdown at Traffic Signals


An overview of London's successful trials

September 2011



Overview

- Introduction
- Developing PCaTS
- PCaTS Trials
- Results
- Conclusion



Introduction: The Need for PCaTS

Pedestrian Understanding of Traffic Signals:

- Green man not understood as *invitation to cross*
- Research indicates around two thirds of pedestrians do not understand the blackout period
- Green man invitation artificially high at some sites in an effort to mitigate the misunderstanding

Mayor's Transport Strategy:

- Smoothing Traffic Flow:
"... Without prejudice to the safety of pedestrians or the needs of other vulnerable road users"



Developing PCaTS

Research


- Review of international use of PCaTS
- Interviews used to develop potential PCaTS designs and canvass public opinion
- Engagement with DfT and HA to understand approvals process for trials and any further implementation

Functionality

- Countdown to red man: reduces pedestrian uncertainty and enables signal optimisation to support Mayor's Transport Strategy



Spreadsheet produced with 300+



Discussions between DfT and TfL

- Ruled out – Countdown with a still red man during the countdown
- Ruled out – Countdown with a flashing green man during the countdown
- Ruled out – 3 aspect vertical solution with countdown numbers in the middle aspect
- Ruled out – A graphic as opposed to a digital countdown
- Ruled out – Animated walking green man during the invitation to cross period or any countdown period
- Ruled out – Separate unit displaying countdown as opposed to joined to the existing two aspect unit.
- Decision – Countdown termination point will be to the start of the still red man

Ref Doc

*PCTS Sol Opt DfT Wkshp 2009-03-09_D
Minutes 9Mar09 - TfL PCTS - Solutions Workshop DTO DfT*

Discussions between DfT and TfL

- Ruled out – Red and green countdown numbers
- Ruled out – Showing a green man with countdown numbers
- Decision – Investigate 3 aspect solution to bolt on side and top/bottom of unit.
- Decision – Investigate flashing amber man at the same time as countdown
- Include – Variation of counting down during the green man invitation to cross on all options

Ref Doc

Minutes 31Mar09 - TfL PCTS - Solutions Options Mtg DTO DfT

Research and DfT/TfL Discussions

- 16 options investigated through interviews and ranked in order of preference.
- Ruled out – 12 options include flashing red, amber or green man stage which interfere with current sequence specified in TSRGD2002
- Ruled out – Countdown numbers at same time of red or green man interfere with current sequence specified in TSRGD2002
- Ruled out – Flashing red man interfere with TSRGD2002
- Ruled out – Flashing amber man interferes with TSRGD2002

Ref Doc

Minutes 5June09 - TfL PCTS - Feedback on Solutions Options Mtg DTO DfT

Minutes 19June09 - TfL PCTS - Decisions on Solutions to take forward DTO DfT

Research and TfL Internal Discussions

- Ruled out options C & D due to proximity to Red Man
- Ruled out option B due to TfL desire for consistency of design with other traffic infrastructure
- Included option E due to mounting possibilities



PCaTS Trials

Off Street Trials

- Conducted at TRL test track using mocked-up crossings with and without PCaTS
- Over 250 pedestrians, including groups of mobility impaired pedestrians involved
- Questionnaires used to establish pedestrians' understanding and opinions of Traffic Signals, including PCaTS



PCaTS Trials – The On Street PCaTS Package

- The trial sites included the installation of a Countdown timer alongside changes to the signal timings at the junctions. This is referred to as the “PCaTS package of measures” and included:
- Reduction in Green Man time to a standard 6 seconds (aligned to DfT guidance)
- Increase in ‘Blackout’ time (with a countdown timer)
- Reduction in ‘All Red’ time (to a standard 3 seconds, with a 2 second starting amber to traffic)
- Increase in traffic green time (as a consequence of the above changes).



PCaTS Trials

On Street Trials



- Approval granted by DfT and HA to conduct on street trials
- TRL commissioned to conduct face to face interviews and video analysis to assess pedestrian perceptions and behaviours
- Sites selected to ensure broad representation of pedestrians included in the research



PCaTS Trials


Trial Sites

	Site number	Site Location
1	08/028	A201 BLACKFRIARS ROAD - B300 THE CUT - B300 UNION STREET
2	10/008	A24 BALHAM HIGH ROAD - CHESTNUT GROVE - BALHAM STATION ROAD
3	03/029	FINSBURY SQUARE - FINSBURY PAVEMENT - CHISWELL STREET
4	08/003	A100 TOWER BRIDGE ROAD - A200 TOOLEY STREET
5	10/160	A306 ROEHAMPTON LANE - QUEEN MARYS HOSPITAL MAIN ACCESS
6	08/211	OLD KENT ROAD - SURREY SQUARE - PENRY STREET
7	02/045	A4200 KINGSWAY - A40 HIGH HOLBORN - A4200 SOUTHAMPTON ROW
8	01/212	OXFORD STREET - REGENT STREET - OXFORD CIRCUS




Results – Pedestrian Perceptions

- The clear majority of pedestrians liked countdown:
 - 83% of the main sample




Results – Pedestrian Perceptions

- The clear majority of pedestrians liked countdown:
 - 94% of the mobility impaired pedestrians




Results – Pedestrian Perceptions

- The clear majority of pedestrians liked countdown:
 - 79% of the young pedestrians liked the countdown numbers




Results – Pedestrian Perceptions

- Preference for PCaTS:
 - Mobility impaired pedestrians and children had the opportunity to compare crossing experience with and without PCaTS – most preferred PCaTS:




Results – Pedestrian Perceptions

- Feeling Rushed:
 - For the main sample the proportion of pedestrians feeling rushed when crossing fell from 39% to 23%:




Results – Pedestrian Perceptions

- Feeling Rushed:
 - Mobility impaired pedestrians and children were asked which crossing they felt least rushed – this was PCaTS crossings for both samples:




Results – Pedestrian Perceptions

- Sufficient time to cross:
 - With PCaTS the percentage of pedestrians feeling they had sufficient time to cross increased from 75% to 88% (despite reduction in invitation to cross):




Results – Pedestrian Perceptions

- Sufficient time to cross:
 - A greater proportion of mobility impaired pedestrians felt they had sufficient time to cross with PCaTS (despite reduction in the invitation to cross):




Results – Pedestrian Perceptions

- Perception of Safety:
 - Although pedestrians felt safe at both types of crossing, more felt safe at PCaTS crossings, increasing from 73 to 91%:




Results – Pedestrian Perceptions

- Perception of Safety:
 - A greater proportion of mobility impaired pedestrians and children reported feeling safe at a PCaTS crossing, compared to a standard crossing:




Results – Pedestrian Crossing Behaviour

- Crossing decisions
 - Generally more pedestrians started to cross at the start of the countdown than in the blackout.
 - Fewer pedestrians started to cross towards the end of the countdown than during the last seconds of the blackout
 - At the point where priority returned to vehicles there was no change in the number of pedestrians remaining on the crossing in the after situation




Results – Pedestrian Behaviour

- Walking Speeds:
 - Walking speeds increased with PCaTS at the three sites where other factors (age and gender of pedestrians) were not significant:



Results – Pedestrian Crossing Behaviour


- The majority of pedestrians crossed as soon as possible after arriving at the junction, in both the before and after situations:
 - 54% crossed within 5 seconds of arrival
 - 70% crossed within 15 seconds of arrival
 - Over 85% had crossed within 30 seconds of arrival



Results – Conflicts

Conflicts measured in 5 categories:

- Level 1: Precautionary - stopping to allow the other road user to pass
- Level 2: Controlled – minor deviation from initial route, or controlled braking
- Level 3: Near Miss – rapid deceleration, lane change or stopping
- Level 4: Very Near Miss – emergency braking or violent swerve
- Level 5: Collision – actual contact between road users (none observed during trial).



Results – Conflicts

Findings

- No level 5 conflicts (collisions) were observed during the trials
- No changes were observed in level 3&4 conflicts (they remained very low)
- Decrease in level 2 conflicts at highest pedestrian flow sites (Oxford St & Kingsway)
- Increase in level 1 (precautionary) conflicts on average across all sites
- Decrease in conflicts overall at Oxford Street



Results – Vehicle observations

- Traffic Benefits:
 - A Linsig model highlights the theoretical capacity increase generated by the PCaTS package:

Site	Capacity Increase		
	AM	IP	PM
08/028	14.3%	18.8%	15.2%
10/008	5.2%	5.0%	4.6%
03/029	20.0%	23.3%	16.4%
08/003	6.1%	5.5%	6.4%
10/160	2.1%	2.5%	2.2%
08/211	3.8%	3.8%	3.8%
02/045	10.7%	11.1%	10.4%
01/212	4.6%	5.3%	4.9%



Results – Vehicle observations




- Traffic Benefits:
 - Turning counts were used to measure the actual capacity benefits created by PCaTS. Due to variations in traffic flows between the before and after situation, these changes do not directly correlate to the theoretical capacity increases:

Site	% difference		
	AM	IP	PM
08/028	25.9%	25.7%	25.0%
10/008	-9.8%	-5.5%	-1.4%
03/029	1.3%	-21.9%	2.6%
08/003	4.4%	5.3%	12.4%
10/160	-3.3%	-10.2%	-20.7%
08/211	13.9%	0.1%	-4.7%
02/045	6.7%	18.0%	15.1%
01/212	1.6%	4.5%	-16.1%



Results – Vehicle observations

- Traffic Benefits:
 - Astrid delay data for 3 sites with an increase in turning counts in all three peaks demonstrates decrease in delay despite increase in vehicles. Effects of Tower Bridge opening explain the delay increase at 08/03 on the Friday:



Results – Vehicle observations

- Traffic Benefits:
 - Typically, vehicle delay saving of around 8% has been achieved by PCaTS, estimated on a conservative basis, disregarding high results at two sites:

Site	Average Delay before	Average Delay after	% difference
08/028	43.86	39.52	-9.9%
10/008	44.09	40.21	-8.8%
08/003	288.86	263.22	-8.9%
10/160	48.12	25.02	-48.0%
08/211	22.4	20.26	-9.6%
02/045	128.1	90.36	-29.5%
01/212	72.9	67.18	-7.8%



Conclusion

This trial has demonstrated that the PCaTS package can deliver benefits to both traffic and pedestrians:

- PCaTS has had a positive response from the public
- PCaTS has reduced pedestrian uncertainty and more informed crossing choices are being made
- With the “PCaTS package” there are significant benefits to traffic
- The “PCaTS package” has been introduced without negative impact to safety



Questions?

